



HOISKO

Kotisi koordinaatit

HOISKO CLT General Instructions 17.11.2016

Packaging

- The building components are delivered wrapped in plastic
- The visible top layer is covered separately with e.g. foam rubber to cover the surface from dirt and damage
- The intermediate floor and the roof units are carried horizontally and the wall units vertically

Assembling

- If needed, the components are equipped with e.g. elevation screws for placing a crane hook or a load strap at the construction site

CNC Machining

- The building components are machined in the factory according to the plans
- The CNC machine has 5 axes, which enables e.g. inclined drilling and other special works
- The CNC machine enables patterns at the top layer

Processes

- The offer is precise when the plans are attached in the request for quotation. The formats for attachments are .pdf and CAD (dwg / ifc). A 3D plan is preferred
- After a contract the customer receives a wall specific drawings for approval
- The customer receives a project specific assembling plan and the delivered material catalogue